



FortyTwo

EVENT PRODUCTION



STAGELINE SL100 MOBILE STAGE

The Stageline SL100 Mobile stage is the workhorse of the small event industry. It allows for full production in a small, economical package without cheapening the look or feel of your event.

Features:

Stage Floor
24' x 20'

Roof Size
25'-1" x 20'-1"

Rigging Height
14'-6"

Stage Deck Height
3'-6" to 4'-0-3"

Load Bearing Capacity
11,800 lbs

Wind Gust Resistance
up to 115 mph

Custom banners, skirts
and drops available

Optional sound wings
and risers

Sets up in 1 hour

For Rental Information, Contact:

Brian Lizzie

Mobile Stage Sales / Production

702-265-2110

blizzie@ftep.net

fortytwoeventpros.com

TECHNICAL SPECIFICATIONS

TRAILER

Length	31' 4" - 34' 9"
Width	8'
Height	11' 2"
Storage Space	23' 6" x 5' 9" x 5' 8"
Storage Compartment	17" x 17" x 36"
Storage Capacity	5000 lb
Weight	9990 lb

STAGE FLOOR

Length And Depth	24' x 20'
Length And Depth With Extension Platforms	40' x 24'
Height	3' 6" to 4' 3"
Design Live Load	100 lb/ft ²
Type Of Surface	Plywood on Aluminum

ROOF

Length And Depth	24' 11" x 23' 9"
Clearance (Inclined Roof)	14' 7" to 13' 9"
Maximum Height With Banner *	23' 11"
Type Of Surface	Fiberglass Bonded on Aluminium
Roof Lifting Capacity	3800 lb
Roof Load Bearing Capacity	6500 lb
4 Built In Rigging Points	350 lb each
2 TRUSSES - Upstage and Downstage (T2)	500 lb
2 Trusses - Central Roof (T1)	700 lb each
2 Front Overhang Extensions* -	125 lb at 34" each
2 Side Overhang Rigging Bars	800 lb at 36" each

PRACTICAL ASPECTS

Personnel Required	1 Certified technician and 2 stagehands
Site Preparation	none
Heavy Machinery Required	none
Mode Of Transportation	1 Fifth-Wheel Tractor or Truck
Gust Wind Resistance	60 mph (97 km/h) With Windwalls 80 mph (129 km/h) Without Windwalls
Rigging Bars - Standard 2" (50 mm) Tubing	Provides Higher Overhead Clearance
Windwalls	Weatherproof - Fire Retardant Vinyl or Scrim
Vertical and Horizontal Banner Supports*	Installed at Ground Level